











standard

CONDENSATE REMOVAL PUMP

Operated by an air conditioning cooling signal, the Standard peristaltic sets the standard for reliability. The remote install options means minimum future maintenance disruption.



6.5L/h max. flow

12m max. head (flow rate 6.5L/h)


KEY FEATURES

- AC cooling signal operated
- Remote install possible
- Pumps contaminated water
- Can run dry

SUITABILITY



- Up to 8.5kW / 29,000Btu/h
- High wall split systems; Ducted units; Floor standing & Chassis units




115mm 115mm 115mm 135 77mm

•

STANDARD SPECIFICATIONS

Max. flow	6.5L/h @ 12m head
Max. head	12m
Max. suction lift	3m
Sound level@1m	47dB(A)
Power supply	230V AC 50-60Hz 0.2A
Rated	Continuously
Class	I appliance
Max. unit output	8.5kW / 29,000Btu/h
Max. water temp	40°C / 104°F
Inlet/outlet	6mm ID
IP Protection	IPX1
Safety switch	n/a
Thermal protection	1
Fully potted	n/a
Self priming	1



SUGGESTED XTRA ACCESSORIES	
Description	Part No.
Peri Spare Tube Kit 🛛	FP1282
1 Amp Fuse	FP2620
Tube To Soil Stack Adaptor	FP2038
For more installation accessories take a look at our Aspen Xtra range	

Standard FP2081/2	STANDA	RD OPTIONS
	Standard	FP2081/2

	IN THE BOX
• Wa	dard pump • 2m Plug & play power cable Il mounted bracket • Fixing kit all manual
•	rownload manual at aspenpumps.com 'iew install video at aspenpumps.com

